



Business Services  
Contracts Office  
5735 47th Avenue • Sacramento, CA 95824  
(916) 643-2464  
Janea Marking, Chief Business Officer  
Robert Aldama, Purchasing Manager II

## ADDENDUM NO. 2

Date: November 1, 2024  
Issued by: Sacramento City Unified School District  
Project: Project #: 25-0116-1  
eRate 28 Cabling Infrastructure

This addenda shall supersede the original Information, attachments, and specifications regarding Project No. 25-0116-1 where it adds to, deletes from, clarifies or otherwise modifies them. All other conditions and any previous addenda shall remain unchanged.

---

### Part A – Bidding and Contract Requirements

#### AD1.01 QUESTIONS

Please clarify the following MDF and all IDFs shall have at least one dedicated 120VAC 20-amp quad-receptacle each. Is this required? This is a NON-E-rate item, Do we provide pricing separately?

#### AD1.01 ANSWER

YES, Provide Separate Pricing.

#### AD1.02 QUESTION

Please clarify the following for all site requiring new single-mode fiber. Part# for LR SFP?

#### AD1.02 ANSWER

All Fiber replacements will require SFP-10G-LR, All Part numbers are found in the Div27 specifications.

#### AD1.03 QUESTION

Please clarify the following. During the site walk it was stated that we are to provide new switches for the following sites 1. Lisbon, 2. Thomas Jefferson, 3. Edward Kelly, 4. OW Erlewine. Can you provide a part#, make and model please?

AD1.03 ANSWER

Switches and any network Equipment will be a made a part of another RFP for Cat2 Equipment. This is for just cabling only.

AD1.04 QUESTION

Please clarify the Following. During the site walk it was stated to include Station Cabling, WAP Cabling, Exterior WAP Cabling, Paging Cabling and Phone Cabling for the following sites: 1. OW Erlewine, 2. Edward Kelly, 3. Thomas Jefferson, 4. Lisbon, Tahoe. Can you please specify the drop count for each technology please?

AD1.04 ANSWER

Go to AD1.11 Answer.

AD1.05 QUESTION

Please clarify the following. Are we to bid the specified footages listed in the RFP?

AD1.05 ANSWER

YES, these are actual distances listed from test results from the existing cabling. Bid accordingly to account for any service loops required.

AD1.06 QUESTION

Please clarify the following. Scope of work for Bear Flag?

AD1.06 ANSWER

Go to AD1.11 Answer.

AD1.07 QUESTION

Please clarify the following. Contractors are to use the existing pathways for all fiber cabling between the MDF and the new or existing IDF locations?

AD1.07 ANSWER

Project No: 25-0116-1  
eRate 28 Cabling Infrastructure  
ADDENDUM NO. 2

AD1.08 QUESTION

Please clarify the following. Are 20 AMP Power Strip 12848-701 required for the new IDF locations?

AD1.08 ANSWER

NO, the part referenced in the question is for floor mounted Racks typically in the MDF. IDFs require a 120VAC 20-amp dedicated circuit with a Quad Outlet receptacle.

AD1.09 QUESTION

Please clarify the following. What type of enclosud

Project No: 25-0116-1  
eRate 28 Cabling Infrastructure  
o2 72 721.56c 0 5

Project No: 25-0116-1  
eRate 28 Cabling Infrastructure  
ADDENDUM NO. 2

1 Cat6 drop to phone location in classroom (locations determined on bid walk).

Project No: 25-0116-1  
eRate 28 Cabling Infrastructure  
ADDENDUM NO. 2

a. Does the payment ETA for each billing procedure differ? If so, how?

AD1.12 ANSWER

E-Rate billing will follow the standard process for E-Rate, Itemized by site.

Non-E-Rate billing will be done as direct billing for the materials and labor.

AD1.13 QUESTION

Please advise if contractors are to provide final cost estimates as:

- a. One lump sum (E-Rate and non-E-Rate combined).
- b. Two lump sums (E-Rate and non-E-Rate separated).
- c. Itemized per campus (regardless of E-Rate vs non-E-Rate).
- d. None of the above; itemization scheme provided by District.

AD1.13 ANSWER

E-Rate Sites can be a lump sum, but must be itemized per ca1-6 (9 (am)-64.3 (or)-6 (es)Tw T /P <</Me1)-6.6 (



Project No: 25-0116-1  
eRate 28 Cabling Infrastructure  
ADDENDUM NO. 2

Yes.

AD1.22 QUESTION

Section 3.05-C-5 of the specifications call for, "MDF and all IDFs shall have at least one dedicated 120VAC 20-amp quad-receptacle each." Please note, high-voltage electrical work is not covered by E-Rate funding, even if it is supporting new network infrastructure: 916-652-4735 P. O. Box 330 Penryn, California 95663-0330 [www.KSTelecomInc.com](http://www.KSTelecomInc.com)

avecnding, e05avecnding, e05

n5.9

(4(52)6(d)10.5

(

t)ba.2

(art



Project No: 25-0116-1  
eRate 28 Cabling Infrastructure  
ADDENDUM NO. 2

Please confirm the copper cabling scope of work for Edward Kelly Pre -School , so the District receives comparable proposals from all bidding contractors:

- a. Data outlet location(s) and quantity of CAT 6 cables per location.

Project No: 25-0116-1

Project No: 25-0116

Project No: 25-0116-1  
eRate 28 Cabling Infrastructure  
ADDENDUM NO. 2

- ii. If no viable electrical panel or open slots exist, are contractors permitted to utilize a nearby existing electrical outlet in lieu of installing a new circuit?
- e. Please confirm if the interior WAPs are to be OFCI (owner furnished, contractor installed).
- f. Please confirm if any exterior WAPs are to be OFCI (owner furnished, contractor installed).
- g. Please confirm if any other devices are to be OFCI (owner furnished, contractor installed).
- i. Any devices not listed are assumed to have cables roughed in, terminated, and tested for future use only. Please advise if this is correct.

AD1.30 ANSWER

The answer is in the narrative of AD1.11.

AD1.31 QUESTION

Please confirm the copper cabling scope of work for Tahoe ES, so the District receives comparable proposals from all bidding contractors:

- a. Data outlet location(s) and quantity of CAT 6 cables per location.
- b. Clock/Speaker location(s) and quantity of CAT 6 cables per location.
- c. Interior WAP location(s) and quantity of CAT 6A cables per location.
- d. Exterior WAP location(s) and quantity of CAT 6A cables per location.
- e. VoIP phone location(s) and quantity of CAT 6 cables per location.
- f. Any additional locations or cables not discussed during the site walks.

AD1.31 ANSWER

The answer is in the narrative of AD1.11.

Project No: 25-0116-1

Project

Project No: 25-0116-1  
eRate 28 Cabling Infrastructure  
ADDENDUM NO. 2

Can the District please provide the contractor furnished and installed Cisco SFP transceiver model numbers, so contractors provide the correct SKU and pricing?

- a. Is the District willing to accept a substitution of 3rd party Cisco-compatible SFP transceivers in lieu of the Cisco SFP model number provided? This could potentially represent a significant cost savings to the District.

AD1.37 ANSWER

All Fiber replacements will require SFP-10G-LR, All Part numbers are found in the Div27 specifications. No non-cisco branded SFP's

AD1.38 QUESTION

Can the District please provide the contractor furnished and installed Cisco switch model numbers, so contractors provide the correct SKU and pricing?

- a. Please confirm if contractors are to perform switch configuration for these new switches.

AD1.38 ANSWER

Switches and any network Equipment will be a made a part of another RFP for Cat2 Equipment. This RFP is just for cabling only.

AD1.39 QUESTION

Please confirm if contractors are responsible for configuration of existing switches

AD1.39 ANSWER

Switches and any network Equipment will be a made a part of another RFP for Cat2 Equipment. This is for just cabling only.

AD1.40 QUESTION

Please advise if contractors are permitted to substitute fiber pigtailed and splice trays in lieu of splice on connectors.

AD1.40 ANSWER

Specification of this defined in the Div27 Structured Cabling.

AD1.41 QUESTION

Is 1-to-1 patching from patch panel to switch an acceptable new IDF layout? This would eliminate the need for horizontal wire management and save rack space

Project No: 25-0116-1  
eRate 28 Cabling Infrastructure  
ADDENDUM NO. 2

AD1.41 ANSWER

Yes, standardized rack layout applies: 24pt/keystone – Switch – 24prt/keystone, using shorter thin-line patch cables.

AD1.42 QUESTION

Are contractors responsible for temporarily relocating any existing furniture that prevent work from occurring, or will the District coordinate those relocations?

AD1.42 ANSWER

Contractor and District will coordinate as needed.

AD1.43 QUESTION

Please confirm if only (1) pair of fiber patch cords (MDF to IDFs) is required for connectivity for each new 24-strand SMFO homerun instaJ 0 Tc 0 Tw 4.j EM (r)-6 ( [(eac)8em 0 Td 9i9o)10J 0l (ac)8.9 (ont)-6.6 (r)-



Project No: 25-0116-1  
eRate 28 Cabling Infrastructure  
ADDENDUM NO. 2

Project No: 25-0116-1  
eRate 28 Cabling Infrastructure  
ADDENDUM NO. 2

AD1.50 QUESTION

Apart from wireless access points, are contractors responsible for providing copper patch cords for station locations, or only the MDF/IDF head ends?

AD1.50 ANSWER

Copper Patch Cords requirements will be included in the Category 2 Equipment RFP to be publish, None are needed for this RFP

AD1.51 QUESTION

Will there be a District assigned material storage area for each campus, or are contractors responsible for storing materials by other means?

AD1.51 ANSWER

Storage of materials will be the responsibility of the Contractor.

AD1.52

Project No: 25-0116-1  
eRate 28 Cabling Infrastructure  
ADDENDUM NO. 2

Project No: 25-0116-1  
eRate 28 Cabling Infrastructure  
ADDENDUM NO. 2

Switches and Core Network Equipment (with 1.2 (f) and 2.0 of 1.1) and RFP (C) 2708.48 (a)