

5735 47th Avenue Sacramento, CA 95824
(916) 643-2464 FAX (916) 643-2190

Jonathan P. Raymond, Superintendent
Patricia A. Hagemeyer, Chief Business Officer

Via Electronic Mail

A D D E N D U M N O . 1

Date: March 28, 2011

Issued by: Sacramento City Unified School District

Project: PC11-700-0151, Leonardo da Vinci Parking Lot Project

You are hereby notified of the following changes, clarifications, or modifications to the original Contract Documents, Specifications, and Drawings. This Addendum shall supersede the original project documents, and shall take precedence over anything to the contrary therein. All Addenda shall be acknowledged in the Bid Form. Failure to do so may result in disqualification of the bid. All other conditions remain unchanged.

Item 1: The Contractor shall make provisions for traffic control including any temporary signing, striping and delineation for proper parking lot operation if permanent signing striping and delineation cannot be completed prior to opening of the parking lot for start of school on Monday, April 25, 2011. Temporary signing, striping and delineation shall consist of pavement tape, temporary glue down paving markers, cones, etc. as required to delineate the traffic flow lanes, bus parking and general parking areas. The vehicle parking areas do not have to have each stall delineated just the general limits of the parking areas. The Contractor shall submit a temporary traffic plan including a list of materials for approval by the District by Wednesday April 13, 2011. The cost for staging of the project to accommodate the opening of the parking lot prior to project completion including additional move-ins for seal coats, signing, striping, delineation and any temporary signing, striping, and delineation shall be included the base bid with no additional compensation allowed there for.

Item 2: Construction Note 15, Sheet 5 is revised as follows:

15. DIGOUT PAVEMENT & REPAIR AREAS SHALL BE MARKED IN THE FIELD BY ENGINEER OR DISTRICT REPRESENTATIVE. APPROXIMATE LOCATIONS ARE SHOWN FOR SAW CUTTING AC, AC/AB REMOVAL, COMPACTION OF EXISTING AB AND INSTALLATION OF 4" AC & 8" AB OVER COMPACTED SUBGRADE. ESTIMATED AREA OF DIGOUT IS 12,000 SF.

This change is shown on Sheet 5 as Revision 1, Addendum No. 1.

Item 3: Construction Note 28, Sheet 5 is revised as follows:

28. INSTALL 4' WIDEx42" HIGH PEDESTRIAN GATE (5 TOTAL) PER DETAIL 10, SHEET 8.

This change is shown on Sheet 5 as Revision 1, Addendum No. 1.



